



Estimating Procedure Tasks

From Ray Herring <rayherring@glass1st.net>

Date Mon 9/14/2026 11:48 AM

To Blake Nicholson <blakenicholson@glass1st.net>

Cc Misael De La Cruz <misaeldelacruz@glass1st.net>

Blake, here is a list for the estimating task manager with times allotted to the task that are dependant upon project size.

1. Project Acceptance and Customer Engagement - .5hr (For Large, Medium, and Small Size Projects)
 - a. Intro Emails
 - b. RFI's
2. Download and Review Project Documents - (Large 3hr, Medium 2hr, Small 1hr)
 - a. Initial review of the drawings to confirm scope
 - b. Review all specifications
 - c. Review Project Manual
 - d. Review Addenda
 - e. Review Project Schedule
 - f. Review Bid Forms
 - g. Create Project Folder
3. Vendor Distribution - .5hr (For Large, Medium, and Small Size Projects)
 - a. Send out RFQ's for Division 7 & 8
4. Plan Set Review & Takeoff - Large 12hrs, Medium 6hrs, Small 3hrs
 - a. Design Criteria
 - i. General Notes
 - ii. Building Code
 - iii. Design Loads
 - iv. Wind Pressures
 - v. Performance Requirements
 - vi. Fire Ratings
 - vii. Accessibility Requirements
 - b. Architectural Drawings Takeoff
 - i. Overall Floor Plans
 - ii. Enlarged Floor Plans
 - iii. Overall Elevations
 - iv. Enlarged Elevations
 - v. Reflected Ceiling Plans
 - vi. Roof Plans
 - vii. Exterior Details
 - c. Details
 - i. Door Schedules
 - ii. Frame Details
 - iii. Window Schedules
 - iv. Curtain Wall Schedules

- v. Finish Schedules
 - vi. Hardware Schedules
 - vii. Glass Schedules
- d. Quantities
 - i. Curtainwall
 - ii. Storefront
 - iii. Windows
 - iv. Entrances
 - v. Doors
 - vi. Glass
 - vii. Louvers
 - viii. Panels
 - ix. Miscellaneous glazing
 - x. Flashings
 - xi. Trim
 - xii. Sealants
 - xiii. Accessories
 - xiv. Verify all quantities against the schedules and drawing details
- e. Review Other Drawing Disciplines
 - i. Structural Drawings
 - ii. Metal Panel Drawings
 - iii. Waterproofing Details
 - iv. Interior Details
- f. Identify Drawing Conflicts
 - i. Drawings and specifications
 - ii. Floor plans and elevations
 - iii. Elevations and details
 - iv. Schedules and details
 - v. Architectural and structural drawings
 - vi. Architectural and mechanical drawings
- g. Missing Information
 - i. Request clarification from the general contractor
 - ii. Submit an RFI if Necessary
- 5. Building the Costing sheet - Large 4hrs, Medium, 2hr, Small 1hr
 - a. Costing Sheet
 - i. Enter all final material pricing
 - ii. Enter all labor hours
 - iii. Enter equipment costs
 - iv. Enter subcontractor costs
 - v. Verify taxes have been applied correctly
 - vi. Review final markups
 - vii. Confirm final selling price prior to proposal submission
 - b. Bond Calculator
 - c. Job recap
 - i. Verify Labor Calculations
 - ii. Enter selected vendor totals
 - iii. Confirm glazing totals
 - iv. Review overall material costs
 - v. Verify labor hours generated from production rates
 - d. Elevation Recap - Enter all dimensions for:
 - i. Storefront

- ii. Window Wall
 - iii. Curtainwall
 - iv. Entrances
 - v. Sunshades
 - vi. Miscellaneous Framing
 - e. Equipment - Enter all anticipated equipment requirements including:
 - i. Boom lifts
 - ii. Scissor Lifts
 - iii. Forklifts
 - iv. Cranes
 - v. Specialized Installation Equipment
 - f. Swing Stage
 - i. Rental Duration
 - ii. Mobilization
 - iii. Installation
 - iv. Removal
 - v. Safety Requirements
 - g. G1 - G11 Glazing Tabs - Responsibilities include:
 - i. Enter Glass Sizes
 - ii. Enter Glazing Quantities
 - iii. Compare Multiple Fabricator quotations
 - iv. Verify Glass make-up
 - v. Verify Low-E Coatings
 - vi. Verify performance requirements
 - vii. Verify specification compliance
 - h. Vendor Quote Management
 - i. Review each quote for specification compliance
 - ii. Verify glass make-up, framing system, finishes, accessories, and exclusions
 - iii. Compare pricing from multiple qualified vendors whenever possible
 - iv. Confirm the quote satisfies the projects design criteria
 - i. Material Lead Times - material lead times shall be requested from every supplier if they are not included with the original quotation. Lead times should be documented to:
 - i. Identify schedule risks
 - ii. Assist business development
 - iii. Support schedule qualifications
 - iv. Coordinate procurement planning
6. Writing the Proposal Large - Large 2hrs, Medium 1hr, Small .5hr
- a. Proposal ID
 - b. Bid Date
 - c. Project Name & Location
 - d. Documents Provided
 - e. Scope & Materials
 - f. Pricing
 - g. Qualifications, Inclusions, & Exclusions
 - h. 1CG Warranty & Disclaimer
 - i. Correspondence to GC capturing the PDF Proposal, Key mentions in the body of the email, and Presentation Packet/Takeoffs of highlighted scope
7. Creating the Presentation Packet - Large 1hr, Medium .5hr, Small .5hr
- a. Cover page
 - b. Preliminary installation schedule
 - c. Highlighted floor plans, elevations, and details

- d. Finish chart
 - e. Product Data
 - i. Glass Type info
 - ii. Every System Type
 - f. Proposal Drawings
 - g. 1CG Fabrications Capabilities
 - h. 1CG Office locations
 - i. 1CG Portfolio Pictures
8. Submissions of the proposal to the customer - .5hr (For Large, Medium, and Small Size Projects)
- a. Bid Forms
9. Following up with Customer 1hr. (For Large, Medium, and Small Size Projects)
- a. Emails for each day.
 - b. Negotiating the Sale
 - c. Comeback Items



Ray Herring

Director of Pre-Construction

C 704.608.6618 | glass1st.net



IMPORTANT: The contents of this email and any attachments are confidential. They are intended for the named recipient(s) only. If you have received this email by mistake, please notify the sender immediately and do not disclose the contents to anyone or make copies thereof.